10. Timber purchased should be removed as early as possible, and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7, *supra*. Timber not removed after purchase, will remain in the Depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, on the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

K. R. VENKATA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the notice issued in pages 1403 and 1404 of Part VI of the *Mysore Gazette*, dated 29th November 1928, calling for tenders for the breach filling of Sondekoppa tank in Nelamangala Taluk.

Last date for receiving tenders 11th December 1928.

R. W. SCALDWELL,
Executive Engineer.

Abstract Notification.

The attention of the public is invited to the notice published on pages 1427—1428 of Part VI of the *Mysore Gazette* dated 6th December 1928, calling for tenders for restoring Horamavu tank of Bangalore Taluk.

The last date for receiving tenders is 11th December 1928.

H. R. VENKATASUBBA RAO,
Executive Engineer.

SPECIAL DIVISION.

Abstract Notification dated 24th November 1928.

The attention of the public is invited to notice calling for tenders for constructing out-houses and workshop attached to the Institute for Defectives in Mysore published in pages 1430 to 1432, Part VI of *Mysore Gazette*, dated 6th December 1928.

V. V. KARVE,
Executive Engineer.

KOLAR DIVISION.

Notice dated 30th November 1928.

The attention of the public is invited to the notification published in the *Mysore Gazette* Part VI, pages 1428 to 1430, dated 6th December 1928, calling for tenders for Restoring Beechagowdanahalli Hongekere tank, Kolar Taluk.

Last date for receipt of tender is 2 P.M. of 3rd January 1929.

Dated 6th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., of 3rd January 1929, for Constructing Matron's quarters and Improving the existing Maternity Hospital at Robertsonpet. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Matron's quarters and Improving the existing Maternity Hospital building at Robertsonpet" in default of which tenders will be rejected.

5. The final acceptance of any tender, will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in figures and words.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower that the estimate will not be accepted.

Abstract estimate for Constructing a Matron's quarters and alterations to the Maternity Hospital at Robertsonpet, Bowringpet Taluk.

Sl. No.	Items of work	Per	Rate	Quantity	Cost	Total
1	Earthwork excavation ...	C.yds.		54		
2	New burnt stone in mortar ...	C.ft.		1,711		
3	Old stone in mortar ...	,,		550		
4	Burnt stone in mud ...	,,		3,241		
5	Burnt stone slabs (6" thick) ...	S.ft.		483		
6	Do ... (old) ...	,,		70		
7	Chunam plastering ...	Sqrs.		34·67		
8	Pointing with mortar (lime) ...	,,		17·62		
9	Fixing the old doors available with necessary repairs.	No.		4		
10	Teakwood panelled doors with irons etc., complete as per Maryot's specification.	S.ft.		90		
11	Fixing old windows with necessary repairs	No.		6		
12	Teakwood ventilators with glazed shutters	S.ft.		45		
13	Cutting old wood to the required size wrought and put up.	C.ft.		70		
14	Teakwood wrought and put up ...	,,		13·45		
15	Roofing with old Mangalore tiles on teak reepers.	Sqrs.		6·00		
16	Roofing with new 1st class Mangalore tiles	,,		13·05		

Sl. No.	Items of work	Per	Rate	Quantity	Cost	Total
17	Old Ridge tiles set in mortar allowing for breakage with cement pointing.	R.ft.		10		
18	New Ridge tiles set in mortar ...	,,		30		
19	Flooring with old cudapah slabs on 3" concrete bed with cement pointing.	Sqr.		8·50		
20	New cudapah slabs flooring on 3" concrete with cement pointing.	,,		2·10		
21	Whitewashing and colour weshing ...	,,		52·29		
22	9" diameter cut stone pillasrs with base and capital 1½' square with cement pointing.	No.		3		
23	Teakwood eave board 9" ...	R.ft.		202		
24	Chunam borders 9" × 4½" ...	,,		56		
25	Silicate painting ...	...		5·88		
26	Wood oiling	Sqr.		11·30		
27	Counstructing sink's and fixing pipes to outlet.	L. S.				
28	Opening out V shaped drain ...	,,				
29	Sundry and unforeseen items ...	,,				
30	Dismantling Damaged portion including filling basement etc., complete as per specification.	,,				
31	Unforeseen items in renewing old materials.	,,				
	Total ...	...				
	Alterations.					
1	Dismantling wall in stone in mortar ...	C.ft.		1,139		
2	Stone in mortar	,,		1,961		
3	Earthwork excavation	C.yd.		10		
4	Archwork stone in mortar ...	C.ft.		92		
5	Teakwood panelled door as per specification	S.ft.		141		
6	Teakwood windows outside panelled inside glazed with iron bars etc., complete as per Maryot's specification.	,,		120		
7	Chunam plastering	Sqr.		24·54		
8	Chunam lime pointing	,,		8·03		
9	Removing mortar ceiling and re-roofing with Mangalore tiles allowing ⅓ for breakages.	...		4·08		
10	Teakwood ceiling ½" plank with screws and wood oiling.	..		7·80		
11	Removing doors and windows and re-fixing and removing bresummers and unforseen works.	L. S.		...		
12	Sundry and unforeseen works ...	,,		...		
	Total ...	...		...		
	Total for both ...	...		...		

Dated 8th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. of 10th January 1929, for Constructing a causeway across the North Pinakini River on Mulbagal-Goribidnur Road near Goribidnur. An approximate estimate of quantities is given below. These quantities are not guaranteed The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 650 (six hundred and fifty only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Constructing a causeway across the North Pinakini River on Mulbagal-Goribidnur Road near Goribidnur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in figures and words.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Estimate of cost of constructing a causeway at 6 & 7—75 of Mulbagal-Goribidnur Road, across the Uttarapinakini River near Goribidnur :—

Serial No.	Items of work	Per	Rate	Quantity	Cost	Total
1	Earthwork excavation	C.yd.		1,987		
2	Burnt stone in surki mortar ...	C.ft.		24,882		
3	Burnt stone slabs 6" thick roughly dressed.	S.ft.		8,976		
4	Burnt stone flooring Suji cut work ...	C.yd.		907		
5	Baling water	Lump	sum			

N. LAKSHMINARASIMHIYA,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

The attention of the public is invited to the notice of calling tenders for restoring Bommarsikoppa Manighatta Tank Reg. No. 202—981 of Sorab Taluk.

M. A. SRINIVASACHARI,
Executive Engineer.

MEDICAL DEPARTMENT.

DISTRICT HOSPITAL, KOLAR.

Dated 29th November 1928.

Sealed tenders in triplicate, on half sheet foolscap size paper will be received at the Office of the District Medical Officer, Kolar, by the undersigned on 5th January 1929 at 11 A.M., for the supply of articles of Bedding and Clothing, required for the use of the District Hospital, Kolar, for the year 1928-29.

For details, please refer to Part VI, page 1413 of the *Mysore Gazette*, dated 29th November 1928.

C. NARAYANA RAO,
District Medical Officer.